

# Public Document Pack



To: Councillor McRae, Convener; Councillor Bouse, Vice-Convener; and Councillors Alphonse, Boulton, Clark, Cooke, Copland, Farquhar, Lawrence, Macdonald, Radley, Tissera and Thomson.

Town House,  
ABERDEEN 13 September 2023

## **PLANNING DEVELOPMENT MANAGEMENT COMMITTEE**

The Members of the **PLANNING DEVELOPMENT MANAGEMENT COMMITTEE** are requested to meet in **Council Chamber - Town House** on **THURSDAY, 21 SEPTEMBER 2023 at 10.00 am**. This is a hybrid meeting and Members may also attend remotely.

The meeting will be webcast and a live stream can be viewed on the Council's website. <https://aberdeen.public-i.tv/core/portal/home>

JENNI LAWSON  
INTERIM CHIEF OFFICER – GOVERNANCE (LEGAL)

### **B U S I N E S S**

**MEMBERS PLEASE NOTE THAT ALL LETTERS OF REPRESENTATION ARE NOW AVAILABLE TO VIEW ONLINE. PLEASE CLICK ON THE LINK WITHIN THE RELEVANT COMMITTEE ITEM.**

#### **MOTION AGAINST OFFICER RECOMMENDATION**

1.1. Motion Against Officer Recommendation - Procedural Note (Pages 5 - 6)

#### **DETERMINATION OF URGENT BUSINESS**

2.1. Determination of Urgent Business

#### **DECLARATION OF INTERESTS AND TRANSPARENCY STATEMENTS**

- 3.1. Members are requested to intimate any declarations of interest or connections

## **REFERRALS FROM COUNCIL, COMMITTEES AND SUB COMMITTEES**

- 4.1. Referral from Full Council - Energy Transition Zone (Pages 7 - 10)

**Members please note that Planning Development Management Committee are only considering point (9) of the approved motion, contained in the minute extract from Full Council.**

## **MINUTES OF PREVIOUS MEETINGS**

- 5.1. Minute of Meeting of the Planning Development Management Committee of 24 August 2023 - for approval (Pages 11 - 24)

## **COMMITTEE PLANNER**

- 6.1. Committee Planner (Pages 25 - 28)

## **GENERAL BUSINESS**

### **WHERE THE RECOMMENDATION IS ONE OF APPROVAL**

- 7.1. Detailed Planning Permission for the erection of student accommodation (circa 383 beds) with associated infrastructure and landscaping - 92-126 Jon Street Aberdeen (Pages 29 - 46)

Planning Reference – 230514

All documents associated with this application can be found at the following link and enter the reference number above:-

[Link.](#)

Planning Officer: Gavin Clark

## **DATE OF NEXT MEETING**

- 8.1. Date of Next Meeting - Thursday 2 November 2023

EHRIAs related to reports on this agenda can be viewed [here](#)

To access the Service Updates for this Committee please click [here](#)

Website Address: [aberdeencity.gov.uk](http://aberdeencity.gov.uk)

Should you require any further information about this agenda, please contact Lynsey McBain, Committee Officer, on 01224 067344 or email [lymcbain@aberdeencity.gov.uk](mailto:lymcbain@aberdeencity.gov.uk)

This page is intentionally left blank

# Agenda Item 1.1

Members will recall from the planning training sessions held, that there is a statutory requirement through Sections 25 and 37 of the Town and Country Planning (Scotland) Act 1997 for all planning applications to be determined in accordance with the provisions of the Development Plan unless material considerations indicate otherwise. All Committee reports to Planning Development Management Committee are evaluated on this basis. It is important that the reasons for approval or refusal of all applications and any conditions to be attached are clear and based on valid planning grounds. This will ensure that applications are defensible at appeal and the Council is not exposed to an award of expenses.

Under Standing Order 29.11 the Convener can determine whether a motion or amendment is competent and may seek advice from officers in this regard. With the foregoing in mind the Convener has agreed to the formalisation of a procedure whereby any Member wishing to move against the officer recommendation on an application in a Committee report will be required to state clearly the relevant development plan policy(ies) and/or other material planning consideration(s) that form the basis of the motion against the recommendation and also explain why it is believed the application should be approved or refused on that basis. The Convener will usually call a short recess for discussion between officers and Members putting forward an alternative to the recommendation.

This page is intentionally left blank

**DRAFT/**

## **COUNCIL**

**11 SEPTEMBER 2023**

The Council had before it a report by the Chief Officer - Corporate Landlord which provided an update on the planning status of sites under Council ownership at Aberdeen South Harbour. The report presented options to collaboratively develop three strategic sites within a strategic partnership with Energy Transition Zone Ltd (ETZ Ltd) and Port of Aberdeen (PoA), owned and operated by Aberdeen Harbour Board (AHB) to drive a transition towards renewable energy technologies and sustainable practices.

### **The report recommended:-**

that the Council -

- (a) note that the Aberdeen Local Development Plan had now been approved and had designated sites at St Fittick's, Gregness and Doonies for development as part of the Energy Transition Zone (ETZ). The three strategic sites made up around 10% of the total ETZ area;
- (b) note that Gregness OP62 and part of St Fittick's OP62 was under the ownership of Aberdeen City Council but leased to the Aberdeen Harbour Board who had an option to purchase this land;
- (c) approve that St Fittick's OP56 and Doonies OP61 be made available to support future investment and development in the ETZ, whilst also improving local amenity;
- (d) instruct the Chief Officer - Corporate Landlord that the St Fittick's OP56 and Doonies OP61 sites were only to be made available for lease and must remain in Council ownership and that, furthermore, any such lease agreement was only to be entered into at the point where financial close was reached on a particular development;
- (e) instruct the Chief Officer - Corporate Landlord to enter formal dialogue with ETZ Ltd and PoA to discuss the optimum partnership arrangements to take forward the future development of the sites and ensure the delivery of the outcomes identified by ETZ Ltd in their masterplan and in Aberdeen's Regional Economic Strategy;
- (f) instruct the Chief Officer - Corporate Landlord, following consultation with the Chief Officer – Finance and Chief Officer - Governance, to consider as part of such potential partnership arrangements how returns from the sites could be re-invested in both the further development of the ETZ and in the local community; and
- (g) instruct the Chief Officer - Corporate Landlord to report the outcome of these discussions to the meeting of the Finance and Resources Committee in December 2023.

Councillor Allard moved, seconded by Councillor Greig:-

That the Council -

- (1) instruct the Chief Officer - Corporate Landlord, in Aberdeen City Council's capacity as land owner, that St Fittick's OP56 and Doonies OP61 sites

- were only to be made available for lease and must remain in Council ownership and that, furthermore, any such lease agreement was only to be entered into at the point where an end user was agreed by Aberdeen City Council and financial close was reached;
- (2) instruct the Chief Officer - Corporate Landlord to enter formal dialogue with ETZ Ltd and PoA to discuss the optimum partnership arrangements to take forward the future development of the sites and ensure the delivery of the outcomes identified by ETZ Ltd in their masterplan and in the North East Regional Economic Strategy and in line with Best Value principles;
  - (3) instruct the Chief Officer - Corporate Landlord, following consultation with the Chief Officer - Finance and Chief Officer - Governance, to consider as part of such potential partnership arrangements how a proportion of the lease income from the sites could be used for the benefit of the local community;
  - (4) agree that approval of any leases was contingent on Council approval of the community benefit package, which was to progress, so far as was practical, parallel with the granting of leases;
  - (5) note that in a recent briefing to elected members of Aberdeen City Council, the Chief Executive of ETZ Ltd wrote: "...we are in advanced discussions with a number of inward investors focused on cable manufacturing, moorings and anchorings, seeking to locate on the site (subject to planning) for these very reasons.";
  - (6) instruct the Chief Officer - Corporate Landlord to engage with PoA, ETZ Ltd, and any other interested party, as to any proposals they had to develop the site, including full details of the development, the rationale for the location of their business and any mitigations proposed to minimise the impact on local residents;
  - (7) note community amenity and wellbeing were key considerations for Aberdeen City Council as the landowner; and instruct the Chief Officer - Corporate Landlord that individual lease agreements must include details of the community impact remediation steps that would be implemented at the termination of the lease;
  - (8) instruct the Chief Officer - Early Intervention and Community Empowerment and Chief Officer - Commercial and Procurement to report through a service update on how the local community may participate in any decision-making process for the disbursement of funds that may be identified for the benefit of communities;
  - (9) **recommend to the Planning Development Management Committee that any future reports of the ETZ Masterplan be reported to the earliest appropriate meeting of Full Council;** and
  - (10) instruct the Chief Officer - Corporate Landlord to report the outcome of discussions regarding St Fittick's OP56 and Doonies OP61 sites to the earliest appropriate meeting of Full Council.

Councillor Watson moved as an amendment, seconded by Councillor Malik:-

That the Council -

- (1) note over 90% of the total area required for the ETZ can be brought forward without the need to develop St Fittick's Park;



- (2) agree that in 2008, Audit Scotland held a “Best Value” Audit into Aberdeen City Council. Agree this report is insufficient for the purposes of deciding on “Best Value” given the following:-
- a. The report does not identify who, if anybody, the Council has spoken to other than ETZ Ltd regarding the use of Council land
  - b. Removing St Fittick’s Park has serious implications for the Council’s aspirations in respect of delivering its Local Outcome Improvement Plan (LOIP) and Anti-Poverty and Inequality strategies which has identified lifting people out of poverty and reducing mental health as one of its key drivers. The report says nothing about any tangible social and economic benefits that will be realised for Torry residents from the proposed officer recommendations. Noting Councillor Allard leads on both the LOIP and the Anti-Poverty and Inequality Committee
  - c. There are no background reports within the report which would give new elected members any additional information required to make an informed decision
  - d. Recommendation (e) of the report is asking Council to enter formal dialogue with ETZ Ltd and others to discuss the optimum partnership arrangements to take forward the future development of the site, noting the legal implications state “Best Value” cannot be determined until discussions take place between the parties. Agree this would mean that “Best Value” for the Council is limited as not all options for “Best Value” have occurred meaning Aberdeen City Council may be selling itself short in both financial and wellbeing terms.

Notwithstanding the above, if elected members are not content to seek the above information before making an informed decision, Council agree the following:-

- (3) approve that Doonies OP61 be made available for lease subject to the Council receiving full commercial rates to support future investment and development in the ETZ, whilst also approving local amenity;
- (4) approve that St Fittick’s OP56 is **NOT** made available for lease or sale;
- (5) instruct the Chief Officer - Corporate Landlord that Doonies OP61 sites are only to be made available for lease subject to the Council receiving market rental value and must remain in Council ownership and that, furthermore, any such lease agreement is only to be entered into with consent of Full Council;
- (6) instruct the Chief Officer - Corporate Landlord to explore all options to identify other potential partners for the site excluding St Fittick’s Park OP56 to ensure the delivery of the outcomes identified in Aberdeen’s Regional Economic Strategy; reporting back to Council in December 2023;
- (7) instruct the Chief Officer - Corporate Landlord, following consultation with the Chief Officer - Finance and Chief Officer - Governance, to consider as part of any potential partnership arrangements how returns from the site could be re-invested in both the further development of the ETZ and in the local community as per (6) above with a report coming back to Council in December 2023; and

- (8) instruct the Chief Officer - Corporate Landlord to submit a progress report on actions in (6) and (7) to the meeting of Council in December 2023.

On a division, there voted:-

For the motion (32) - Lord Provost; Depute Provost; and Councillors Al-Samarai, Allard, Alphonse, Boulton, Bouse, Brooks, Hazel Cameron, Clark, Cooke, Copland, Cormie, Crockett, Cross, Davidson, Fairfull, Farquhar, Greig, Henrickson, Hutchison, MacGregor, McLellan, McLeod, McRae, Massey, Mennie, Nicoll, Radley, Mrs Stewart, van Sweeden and Yuill.

For the amendment (12) - Councillors Ali, Blake, Bonsell, Graham, Grant, Kuszniir, Lawrence, Macdonald, Malik, Thomson, Tissera and Watson.

Absent from the division (1) - Councillor Houghton.

**The Council resolved:-**  
to adopt the motion.

## PLANNING DEVELOPMENT MANAGEMENT COMMITTEE

ABERDEEN, 24 August 2023. Minute of Meeting of the PLANNING DEVELOPMENT MANAGEMENT COMMITTEE. Present:- Councillor McRae, Convener; Councillor Bouse, Vice Convener; and Councillors Allard (as substitute for Councillor Radley for articles 1 to 3), Alphonse, Blake, Boulton, Clark, Cooke, Copland, Farquhar, Lawrence, Radley (for articles 4 to 6) and Thomson.

The agenda and reports associated with this minute can be found [here](#).

Please note that if any changes are made to this minute at the point of approval, these will be outlined in the subsequent minute and this document will not be retrospectively altered.

### MINUTE OF MEETING OF THE PLANNING DEVELOPMENT MANAGEMENT COMMITTEE OF 29 JUNE 2023

1. The Committee had before it the minute of the previous meeting of 29 June 2023, for approval.

**The Committee resolved:**

to approve the minute as a correct record.

### COMMITTEE PLANNER

2. The Committee had before it the committee business planner, as prepared by the Interim Chief Officer – Governance (Legal).

**The Committee resolved:-**

- (i) to note the reason for the delay in regards to item 8 (Land at Greenferns sites OP28 and OP33); and
- (ii) to otherwise note the committee business planner.

### THE JAMES HUTTON INSTITUTE, COUNTESSWELLS ROAD, ABERDEEN - 221419

3. The Committee had before it a report by the Chief Officer – Strategic Place Planning, **which recommended:-**

That the application for Detailed Planning Permission for the formation of access road, amended car parking and associated drainage at the James Hutton Institute, Countesswells Road Aberdeen, be approved subject to the following conditions:-

**Conditions**

**PLANNING DEVELOPMENT MANAGEMENT COMMITTEE**

24 August 2023

**(01) DURATION OF PERMISSION**

The development to which this notice relates must be begun not later than the expiration of 3 years beginning with the date of this notice. If development has not begun at the expiration of the 3-year period, the planning permission lapses.

Reason - in accordance with section 58 (duration of planning permission) of the 1997 act.

**(02) TREE PROTECTION FENCING**

No development (including site setup) shall take place unless the tree protection measures shown in Tree Survey JHIC-2211-TRA-A (dated 17 March 2023) and drawing JHIC-22-11-TP (Rev.A) by Astell Associates (or such other details and drawing which may be approved by the planning authority for the same purpose) have been implemented. Thereafter the fencing shall remain in place for the duration of construction of the development.

Reason – to protect trees and vegetation from damage during construction in accordance with Policy NE5 (Trees and Woodlands).

**(03) INVASIVE NON-NATIVE SPECIES**

No development shall take place unless an invasive non-native species management plan has been submitted to and approved in writing by the planning authority. The plan shall include details of measures designed to minimise the risk of non-native species being spread during construction activities within the application site. Thereafter, construction shall be undertaken in accordance with the approved plan.

Reason – to control the spread of invasive non-native species during construction.

**(04) LANDSCAPING AND COMPENSATORY TREE PLANTING**

No development shall take place unless a detailed scheme of landscaping for the site has been submitted to and approved in writing by the planning authority. The scheme shall include tree/shrub planting numbers, densities, locations, species, sizes, and stage of maturity at planting.

Thereafter all planting, seeding and turfing comprised in the approved scheme of landscaping shall be carried out in the first planting season following the completion of the development and any trees or plants which within a period of five years from the completion of the development die, are removed or become seriously damaged or diseased shall be replaced in the next planting season with others of a size and species similar to those originally required to be planted, or in accordance with such other scheme as may be submitted to and approved in writing for the purpose by the planning authority.

**PLANNING DEVELOPMENT MANAGEMENT COMMITTEE**

24 August 2023

Reason – to satisfactorily integrate the development into its surroundings and maintain the visual amenity of the area.

(05) TRAVEL PLAN

The junction and road hereby approved shall not be brought into use unless a travel plan for the campus has been submitted to and approved in writing by the planning authority. The travel plan shall outline sustainable measures to deter the use of the private car, in particular single occupant trips and provides detailed monitoring arrangements and modal split targets.

Thereafter the travel plan shall be implemented.

Reason – to encourage more sustainable forms of travel to campus.

(06) DRAINAGE

The junction and road hereby approved shall not be brought into use unless all surface water drainage works detailed in the approved Drainage Assessment (140950 - DA01 (Rev.2) and drawing 140950/2000 (Rev.E) produced by Fairhurst (or such other drawing approved for the purpose) have been installed in accordance with the approved details and is available for use.

Reason – to safeguard water qualities, prevent flooding and ensure that the junction and road can be adequately drained.

The Committee heard from Matthew Easton, Senior Planner, who spoke in furtherance of the application and answered various questions from Members.

The Committee then heard from Mirjam Brady-van den Bos, Coleen Murphy, Ellen Robinson and Heather Turnbull, who all objected to the application and requested that the application be refused.

A statement was read out by the clerk on behalf of Paul Howlett and Neil McDonald, who also both objected to the application.

The Committee then heard from Alasdair Cox, applicant, who spoke in support of the application.

The Convener moved, seconded by the Vice Convener:-

That the application be approved conditionally in line with the officers recommendation with an extra condition added to read:-

“LANDSCAPING, BIODIVERSITY ENHANCEMENT AND COMPENSATORY TREE PLANTING

**PLANNING DEVELOPMENT MANAGEMENT COMMITTEE**

24 August 2023

No development shall take place unless a detailed scheme of landscaping for the site and screening of the area between the new access road and rear of homes at Macaulay Grange has been submitted to and approved in writing by the planning authority. The scheme shall include –

- (i) Existing landscape vegetated areas to be retained, including proposed protection measures;
- (ii) The location of new trees, shrubs, hedges, grassed / wildflower areas;
- (iii) A schedule of planting to comprise species, plant sizes and proposed numbers and density;
- (iv) The location, design and specification of biodiversity enhancement measures;
- (v) A programme for the implementation and subsequent maintenance of the proposed landscaping.

Thereafter all planting, seeding and turfing comprised in the approved scheme of landscaping shall be carried out in the first planting season following the completion of the development and any trees or plants which within a period of five years from the completion of the development die, are removed or become seriously damaged or diseased shall be replaced in the next planting season with others of a size and species similar to those originally required to be planted, or in accordance with such other scheme as may be submitted to and approved in writing for the purpose by the planning authority.

Reason – to satisfactorily integrate the development into its surroundings, help screen the development from homes at Macaulay Grange and maintain the visual amenity of the area.

Councillor Boulton, seconded by Councillor Farquhar, moved as an amendment:-

That the application be refused as the loss of trees and woodlands would be contrary to policies 1, 3, 4 and 6 of National Planning Framework 4 and policies NE3 and NE5 of the Aberdeen Local Development Plan by virtue of the adverse effects on biodiversity, landscape, amenity and climate.

The additional access onto Countesswells Road would have an adverse impact on pedestrian and traffic safety due to the proximity to the nearby primary school and due to driveways immediately opposite which would result in a breach of the guidance in the interim Aberdeen Planning Guidance on Transport and Accessibility.

On a division, there voted – for the motion (7) – the Convener, the Vice Convener and Councillors Allard, Alphonse, Cooke, Copland and Lawrence – for the amendment (5) – Councillors Blake, Boulton, Clark, Farquhar and Thomson.

**The Committee resolved:-**

to approve the application conditionally.

**PLANNING DEVELOPMENT MANAGEMENT COMMITTEE**

24 August 2023

**53 ERSKINE STREET ABERDEEN - 230582**

4. The Committee had before it a report by the Chief Officer – Strategic Place Planning, **which recommended:-**

That the application for Detailed Planning Permission for the change of use of flat to short term let accommodation (sui generis) with maximum occupancy of two people at Ground Floor Right, 53 Erskine Street Aberdeen, be approved subject to the following conditions: -

**Conditions**

(1) DURATION OF PERMISSION

The development to which this notice relates must be begun not later than the expiration of 3 years beginning with the date of this notice. If development has not begun at the expiration of the 3-year period, the planning permission lapses.

Reason - in accordance with section 58 (duration of planning permission) of the 1997 act.

(2) TIME LIMIT FOR SHORT-TERM LET USE

The hereby approved use of the property as Short-Term Let accommodation shall expire 5 years following the date of the grant of permission as stated on this notice, unless a further planning permission has been granted for continued use of the property as Short-Term Let accommodation in the meantime. Should no further planning permission be granted then the property shall revert to mainstream residential use as a flat after the aforementioned 5-year period.

Reason: In order to allow the local housing need and demand situation and the local economic benefits derived from the use of the property as a Short Term Let to be reassessed in 5 years' time, to ensure that the loss of the property as residential accommodation would remain compliant with Policy 30 of NPF4.

The Committee heard from Alex Ferguson, Senior Planner, who spoke in furtherance of the application and answered various questions from Members.

The Committee then heard from Sophie Morrison, applicant, who spoke in support of the application.

**The Committee resolved:-**

to approve the application conditionally.

**PLANNING DEVELOPMENT MANAGEMENT COMMITTEE**

24 August 2023

**AIRYHALL DISTRIBUTION SERVICE RESERVOIR, CRAIGTON ROAD, ABERDEEN  
- 230212**

5. The Committee had before it a report by the Chief Officer – Strategic Place Planning **which recommended:-**

That the application for Detailed Planning Permission for the installation of tank mounted solar PV arrays and associated equipment at Airyhall Distribution Service Reservoir, Craigton Road Aberdeen, be approved subject to the following conditions:-

**Conditions**

(01) DURATION OF PERMISSION

The development to which this notice relates must be begun not later than the expiration of 3 years beginning with the date of this notice. If development has not begun at the expiration of the 3-year period, the planning permission lapses.

Reason - in accordance with section 58 (duration of planning permission) of the 1997 act.

(02) SITE RESTORATION

On the solar arrays hereby approved no longer being used for the purposes of generating electricity, (i) the planning authority must be notified; and (ii) within six months the solar arrays and supporting frames shall be removed from the site and land restored to its condition before the development took place or such other state as may be agreed with the planning authority.

Reason – to minimise unnecessary visual intrusion for surrounding residents.

The Committee heard from Matthew Easton, Senior Planner, who spoke in furtherance of the application and answered various questions from Members.

The Committee then heard from Mark Gordon who objected to the application.

The Committee then heard from Roddy Spiers, applicant, who spoke in support of the application.

**The Committee resolved:-**

to approve the application conditionally with an extra condition added to read:-

(3) LANDSCAPING AND BIODIVERSITY ENHANCEMENT

No development shall take place unless a detailed scheme of landscaping for the site and screening of the areas between the solar arrays and surrounding residential properties (taking into account the operational nature of the site) has



**PLANNING DEVELOPMENT MANAGEMENT COMMITTEE**

24 August 2023

been submitted to and approved in writing by the planning authority. The scheme shall include –

- (i) The location of new trees, shrubs, hedges, grassed / wildflower areas;
- (ii) A schedule of planting to comprise species, plant sizes and proposed numbers and density;
- (iii) The location, design and specification of biodiversity enhancement measures;
- (iv) A programme for the implementation and subsequent maintenance of the proposed landscaping.

Thereafter all planting and seeding comprised in the approved scheme of landscaping shall be carried out in the first planting season following the completion of the development and any trees or plants which within a period of five years from the completion of the development die, are removed or become seriously damaged or diseased shall be replaced in the next planting season with others of a size and species similar to those originally required to be planted, or in accordance with such other scheme as may be submitted to and approved in writing for the purpose by the planning authority.

Reason – to satisfactorily integrate the development into its surroundings, help screen the development from homes at Macaulay Drive and maintain the visual amenity of the area.

**SITE OF FORMER CORDYCE SCHOOL, RIVERVIEW DRIVE, DYCE, ABERDEEN - 221232**

**6.** The Committee had before it a report by the Chief Officer – Strategic Place Planning **which recommended:-**

That the application for Detailed Planning Permission for the erection of 91 homes including associated infrastructure, open space and landscaping at the site of the former Cordyce School, Riverview Drive Aberdeen, be approved subject to a legal agreement and subject to the following conditions:-

**Conditions**

(01) DURATION OF PERMISSION

The development to which this notice relates must be begun not later than the expiration of 3 years beginning with the date of this notice. If development has not begun at the expiration of the 3-year period, the planning permission lapses.

Reason - in accordance with section 58 (duration of planning permission) of the 1997 act.

**PLANNING DEVELOPMENT MANAGEMENT COMMITTEE**

24 August 2023

**(02) MATERIALS**

That no development shall take place unless a scheme detailing all external finishing materials to the roofs, walls, doors and windows of the development hereby approved has been submitted to, and approved in writing by, the planning authority and thereafter the development shall be carried out in accordance with the details so agreed.

Reason: In the interests of visual amenity.

**(03) TREE PROTECTION MEASURES (01)**

That no development shall take place unless all tree protection measures as shown on drawing 375340-QGIS010/Rev002 by EnviroCentre, dated 31st March 2023 have been erected. Once in place, all tree protection measures shall remain in situ until all construction work associated with the hereby approved development has been completed and all plant and machinery has been removed from site.

Reason: In order to ensure adequate protection for the trees on site during the construction of the development.

**(04) TREE PROTECTION MEASURES (02)**

That no materials, supplies, plant, machinery, spoil, changes in ground levels or construction activities shall be permitted within the protected areas specified in the aforementioned scheme of tree protection without the written consent of the Planning Authority and no fire shall be lit in a position where the flames could extend to within 5 metres of foliage, branches or trunks.

Reason: To ensure adequate protection for the trees on site during the construction of the development.

**(05) LANDSCAPING (SPECIES)**

That no development shall take place until details of all tree species to be planted as part of the landscaping scheme hereby approved have been submitted and agreed in writing by the Planning Authority. Subsequently, only the tree species as set out in the hereby agreed details shall be planted as part of the agreed landscaping scheme.

Reason: To ensure no conflict with safeguarding criteria of Aberdeen International Airport.

**(06) LANDSCAPING (IMPLEMENTATION AND MAINTENANCE)**

All soft and hard landscaping proposals shall be carried out in accordance with the approved scheme as shown on drawings 415.45.01b; 415.45.02b; 415.45.03b; 415.45.04b; 415.45.05b; 415.45.06b; and 415.45.07b, all by EnviroCentre and dated August 2023, with tree species as agreed as part of condition 5 as set out above, and

**PLANNING DEVELOPMENT MANAGEMENT COMMITTEE**

24 August 2023

shall be completed during the planting season immediately following the commencement of the development or as otherwise agreed in writing with the Planning Authority.

Any planting which, within a period of 5 years from the completion of the development, in the opinion of the Planning Authority is dying, being severely damaged or becoming seriously diseased, shall be replaced by plants of similar size and species to those originally required to be planted.

Thereafter, all management and maintenance of the landscaped and open space areas as shown on in the 'Maintenance' schedule on drawing 415.45.02b, by EnviroCentre and dated August 2023 shall be implemented, in perpetuity, in accordance with the approved programme.

Reason: To ensure the implementation of a satisfactory scheme of landscaping which will help to integrate the proposed development into the local landscape in the interests of the visual amenity of the area and to ensure that the landscaping is managed and maintained in perpetuity.

**(07) PLOT BOUNDARIES (IMPLEMENTATION)**

That no individual plot hereby approved shall be occupied until all relevant plot boundary enclosures as shown on drawings A1-90-02/RevC for that plot have been implemented in their entirety unless otherwise agreed in writing by the planning authority. For the avoidance of doubt, this shall include the specification as set out in Section 7.3 on page 20 of the submitted Noise Impact Assessment by EnviroCentre, dated April 2023 for acoustic barriers fences to plots 1 through to 15 and plots 70 through to 73, unless otherwise agreed in writing.

Reason: In the interest of visual and residential amenity.

**(08) NOISE MITIGATION MEASURES**

That no residential unit hereby approved shall be occupied unless fitted with glazing and trickle vents as specified in section 7.4 on page 20 of the of the submitted Noise Impact Assessment by EnviroCentre, dated April 2023 or such other specification as may subsequently be submitted and approved in writing by the planning authority.

Reason: In the interest of residential amenity.

**(09) CAR PARKING (IMPLEMENTATION)**

That plots 70 through to 91 of the development hereby approved shall not be occupied unless the related car parking areas have been constructed, drained, laid-out and demarcated in accordance with drawing A1-90-03/RevA, by the Architecture and Planning, dated 10<sup>th</sup> May 2023 or such other drawing as may subsequently be submitted and approved in writing by the planning authority. Such areas shall not thereafter be used for any other purpose than the parking of cars ancillary to the development.

**PLANNING DEVELOPMENT MANAGEMENT COMMITTEE**

24 August 2023

Reason: In the interests of public safety and the free flow of traffic.

(10) EV CHARGING

That no development shall take place until a detailed scheme of electric vehicle charging infrastructure has been submitted to and approved in writing by the Planning Authority. The scheme shall take account of the requirements of section 7.2 (Electric Vehicle Charging) of the Building Standards Domestic Technical Handbook (June 2023) and show the location and specification of active and passive charging infrastructure. Thereafter, unless otherwise agreed in writing with the Planning Authority, no unit within the development shall be occupied unless the scheme for that particular plot has been implemented and charging points are available for use.

Reason: To future proof the site to increase the use of electric vehicles.

(11) RESIDENTIAL TRAVEL PLAN

That no residential unit hereby approved shall be occupied until a Residential Travel Pack has been submitted and approved in writing by the Planning Authority. Such approved packs shall subsequently be issued to the first occupiers of each residential unit.

Reason: To promote sustainable travel methods

(12) PEDESTRIAN CROSSING AND BUS STOP

That no development shall take place until a scheme detailing the relocation and upgrading of the existing bus stops on Riverview Drive; and installation of a signalised pedestrian/cycle crossing on Riverview Drive has been submitted to and approved in writing by the Planning Authority. Subsequently, no residential unit shall be occupied until the approved scheme has been implemented in its entirety.

Reason: In the interest of public safety and to ensure delivery of a safe route to school.

(13) LOW AND ZERO CARBON BUILDING AND WATER EFFICIENCY

No development shall take place until a scheme detailing compliance with policy R6 (Low and Zero Carbon Building and Water Efficiency) of the 2023 Aberdeen Local Development Plan has been submitted to and approved in writing by the Planning Authority. Thereafter, no residential unit shall be occupied unless any recommended measures specified in that scheme for the reduction of carbon emissions and water efficiency have been implemented.

Reason: To ensure that the development complies with requirements for reductions in carbon emissions and water efficiency as specified in policy R6 (Low and Zero Carbon Buildings and Water Efficiency) of the 2023 Aberdeen Local Development Plan.

**PLANNING DEVELOPMENT MANAGEMENT COMMITTEE**

24 August 2023

**(14) PROGRAMME OF ARCHAEOLOGICAL WORKS**

No development shall take place until an archaeological written scheme of investigation (WSI) has been submitted to and approved in writing by the Planning Authority. The WSI shall include details of how the recording and recovery of archaeological resources found within the application site shall be undertaken, and how any updates, if required, to the WSI will be provided throughout the implementation of the programme of archaeological works. Should the archaeological works reveal the need for post excavation analysis the development hereby approved shall not be occupied unless a post excavation research design (PERD) for the analysis, publication and dissemination of results and archive deposition has been submitted and approved in writing by the Planning Authority and the PERD has been carried out in complete accordance with the approved details unless otherwise agreed in writing with the Planning Authority.

Reason: To safeguard and record the archaeological potential of the area.

**(15) DUST MANAGEMENT**

No development shall take place until:

- (a) An Air Quality (Dust) Risk Assessment by a suitably qualified consultant has been submitted to and agreed in writing by the Planning Authority. This Air Quality (Dust) Risk Assessment shall be carried out in accordance with Guidance on the Assessment of Dust from Demolition and Construction by the Institute of Air Quality Management (IAQM) to predict the likely dust levels and impact on air quality including a determination of its significance; and
- (b) A Dust Management Plan (based on the results of the Air Quality (Dust) Risk Assessment) detailing the necessary dust control measures to be implemented, has been submitted to and agreed in writing by the Planning Authority.

Thereafter the development shall be carried out in accordance with the agreed details.

Reason: In the interest of residential amenity

**(16) INTRUSIVE GROUND INVESTIGATION**

No development shall take place until an intrusive ground investigation to establish if contamination is present has been submitted to and approved in writing by the Planning Authority. Thereafter, no residential unit shall be occupied unless any necessary remediation has been carried out in accordance with the agreed details.

Reason: In the interest of public health.

**(17) EXTERNAL LIGHTING SCHEME**

No development shall take place until a detailed scheme of all external lighting proposed for the site has been submitted to and approved in writing by the Planning Authority.

**PLANNING DEVELOPMENT MANAGEMENT COMMITTEE**

24 August 2023

Thereafter, any external lighting installed outwith individual residential curtilages shall be in accordance with the agreed details.

Reason: To assist in the protection of protected species.

(18) PLAY AREAS

That prior to the occupation of the 60th residential unit hereby approved both the informal play area (kickabout space) and the equipped play space as shown on drawings 415.45.06b and 415.45.07b, both by EnviroCentre, dated May 2023 shall be installed in accordance with details shown on these drawings and are available for use, unless otherwise agreed in writing by the Pplanning Authority.

Reason: To ensure sufficient play spaces are available to serve the residents of the development.

(19) PROTECTED SPECIES

No development (including demolition) shall take place until all mitigation/ compensation measures as set out in section 4.2 on page 10 of the Otter and Bat Survey by EnviroCentre and dated April 2023; and the section 'Good Practice Mitigation and Compensation' on page 3 of the 'Mammal Burrow Monitoring' document by EnviroCentre and dated 11 October 2022 have been, or are being, implemented in accordance with the approved scheme.

Reason: To ensure no adverse impact on protected species.

(20) BAT ROOST POTENTIAL SURVEY

Prior to the removal of any trees on site, a further bat roost survey to determine the character of tree cavities and to identify the presence/absence of bats in trees which host potential roost features should be undertaken, submitted to and approved in writing by the Planning Authority. If any bats are identified, then the affected tree(s) shall not be removed unless a mitigation plan has been submitted and agreed in writing by the Planning Authority. Thereafter, the agreed mitigation plan shall be implemented.

Reason: To ensure no adverse impact on protected species.

The Committee heard from Dineke Brasier, Senior Planner, who spoke in furtherance of the application and answered various questions from Members.

**The Committee resolved:-**

to approve the application conditionally subject to a legal agreement and an extra condition added to read:-

**PLANNING DEVELOPMENT MANAGEMENT COMMITTEE**

24 August 2023

(21) CONSTRUCTION ENVIRONMENTAL MANAGEMENT PLAN

That no development shall take place unless there has been submitted to, and approved in writing by the Planning Authority a Construction Environmental Management Plan which includes measures to ensure that no pollution (in particular sediment and silt) enters the unnamed watercourse to the north boundary or the river Don. The development shall be carried out in complete accordance with such plan as so approved.

Reason: To prevent pollution of watercourses

- **Councillor Ciaran McRae, Convener**

This page is intentionally left blank



	A	B	C	D	E	F	G	H	I
1	<b>PLANNING DEVELOPMENT MANAGEMENT COMMITTEE BUSINESS PLANNER</b> The Business Planner details the reports which have been instructed by the Committee as well as reports which the Functions expect to be submitting for the calendar year.								
2	Report Title	Minute Reference/Committee Decision or Purpose of Report	Update	Report Author	Chief Officer	Directorate	Terms of Reference	Delayed or Recommended for removal or transfer, enter either D, R, or T	Explanation if delayed, removed or transferred
3			<b>21 September 2023</b>						
4	92-126 John Street - 230514	To approve or refuse the application for the erection of student accommodation (circa 383 beds) with associated infrastructure and landscaping		Gavin Clark	Strategic Place Planning	Place	1		
5	<b>PRE APPLICATION FORUM</b> - Land At Rigifa Farm Cove Road Aberdeen	To hear from the applicant in relation to proposed battery storage units with associated infrastructure, control and switch containers and associated works		Gavin Clark	Strategic Place Planning	Place			
6			<b>02 November 2023</b>						
7	Committee Annual Effectiveness Report	To report on the annual effectiveness for the period 14 October 2022 to 14 October 2023.		Lynsey McBain	Governance	Commissioning	GD8.5		
8	259 Union Street - 230246	To approve or refuse the application for change of use from office to student accommodation (sui generis) including refurbishment and replacement of windows, alterations of vents and associated works		Laura Robertson	Strategic Place Planning	Place	1		
9	Land At Greenferns Sites OP28 & OP33	To approve or refuse the application for Residential-led, mixed use development comprising approximately 1,650 homes, employment use, a neighbourhood centre comprising local retail and commercial provision, leisure and community uses and associated infrastructure including new and upgraded access roads, landscaping, open space and engineering works		Gavin Clark	Strategic Place Planning	Place	1		


	A	B	C	D	E	F	G	H	I
	Report Title	Minute Reference/Committee Decision or Purpose of Report	Update	Report Author	Chief Officer	Directorate	Terms of Reference	Delayed or Recommended for removal or transfer, enter either D, R, or T	Explanation if delayed, removed or transferred
2									
10	Former Banks o'Dee Nursing Home, Abbotswell Road - 230685	To approve or refuse the application for conversion to 24 affordable flats, installation of replacement windows and doors, cladding, alterations to car park and garden ground		Alex Ferguson	Strategic Place Planning	Place	1		
11	Former Aberdeen Market And 91-93 Union Street - 230704	To approve or refuse the application for Replacement of Aberdeen Market (including redevelopment of 91-93 Union Street) with mixed use development including retail (class 1A), food and drink (class 3), leisure (class 11), and landscaping / public open space including proposed pedestrian link from Union Street to the Green, and associated works		Matthew Easton	Strategic Place Planning	Place	1		
12	Energy Transition Zone - public consultation	At the meeting on 29 June 2023, it was agreed (a) to approve the content of the draft ETZ Masterplan (Appendix 1); (b) instructs the Chief Officer – Strategic Place Planning to, subject to any minor drafting changes, publish the draft ETZ Masterplan for a six week period of non statutory public consultation; and (c) to instruct the Chief Officer – Strategic Place Planning to report the outcomes of the public consultation and any proposed revisions to the draft ETZ Masterplan to a subsequent Planning Development Management Committee within the next six months.		Laura Robertson	Strategic Place Planning		4 and 5		
13			<b>07 December 2023</b>						
14	Procedure for Representations	At the meeting of PDMC on 3 November 2022, a new draft procedure was agreed for allowing representations to speak at Committee. It was agreed to instruct the Chief Officer – Strategic Place Planning to report back to the Committee on the effectiveness of the Procedure by December 2023.		Alan Thomson	Strategic Place Planning	Place	5		
15			<b>Future applications to PDMC (date of meeting yet to be finalised.</b>						
16	Aberdeen Grammar School FP's Club, 86 Queens Road - 211806	To approve or refuse the application for erection of 3no. villas, 4no. apartments and 2no. maisonette apartments with associated works		Jane Forbes	Strategic Place Planning	Place	1		

	A	B	C	D	E	F	G	H	I
	Report Title	Minute Reference/Committee Decision or Purpose of Report	Update	Report Author	Chief Officer	Directorate	Terms of Reference	Delayed or Recommended for removal or transfer, enter either D, R, or T	Explanation if delayed, removed or transferred
2									
17	Summerhill Church Stronsay Drive - 220990	To approve or refuse the application for redevelopment of church and manse site for residential development (14 dwellings)		Lucy Greene	Strategic Place Planning	Place	1		
18	Waterton House Abereen - 230297	To approve or refuse the application for PPP for 16 residential plots		Lucy Greene	Strategic Place Planning	Place	1		
19	Rosehill House, Ashgrove Rd West - 230414	To approve or refuse the application for McDonald's Restaurant with drive thru		Lucy Greene	Strategic Place Planning	Place	1		
20	56 Park Road - 221074	To approve or refuse the application for the erection of 30 flats		Robert Forbes	Strategic Place Planning	Place	1		
21	Woodend - Culter House Road - 210889	To approve or refuse the application for erection of 19no. self-build dwelling houses with associated landscaping, access and infrastructure		Dineke Brasier	Strategic Place Planning	Place	1		
22	26 Rubislaw Den North - 230665	To approve or refuse the application for erection of single storey extension, window replacement to rear; and installation of two new gates to front		Rebecca Kerr	Strategic Place Planning	Place	1		
23	Former Cults Railway Station Station Road Cults - 230772	To approve or refuse the application for change of use from class 4 (business) to class 1A (shops and financial professional and other services) and class 3 (food and drink) with covered outdoor seating area including demolition of existing lean-to extension and erection of single storey extension; alterations to a shop front; re-cladding; installation of doors, rooflights and roof repairs with associated car parking and other associated works		Gavin Clark	Strategic Place Planning	Place	1		
24	Former Cults Station, Station Road, Cults - 230922	To approve or refuse the application for retention of takeaway food kiosk and outdoor seating area with decking including change of use (temporary for 12 months)		Gavin Clark	Strategic Place Planning	Place	1		

This page is intentionally left blank

 <p><b>ABERDEEN</b> CITY COUNCIL</p>	<h2 style="margin: 0;">Planning Development Management Committee</h2> <p style="margin: 5px 0 0 0;">Report by Development Management Manager</p> <p style="margin: 5px 0 0 0;"><b>Committee Date:</b> 21st September 2023</p>
---	---

<b>Site Address:</b>	92-126 John Street, City Centre, Aberdeen, AB25 1LE
<b>Application Description:</b>	Erection of student accommodation (circa 383 beds) with associated infrastructure and landscaping
<b>Application Ref:</b>	230514/DPP
<b>Application Type</b>	Detailed Planning Permission
<b>Application Date:</b>	4 May 2023
<b>Applicant:</b>	Levelling Up Real Estate Ltd
<b>Ward:</b>	George Street/Harbour
<b>Community Council:</b>	George Street
<b>Case Officer:</b>	Gavin Clark



© Crown Copyright. Aberdeen City Council. Licence Number: 100023401 – 2023

### RECOMMENDATION

Approve Conditionally and Subject to Legal Agreement

## **APPLICATION BACKGROUND**

### **Site Description**

The application site is located to the immediate north of the city centre boundary and incorporates a site extending to approximately 0.47 hectares on the northern side of John Street. The site is largely vacant and was previously occupied by since demolished 3 ½ storey tenement buildings, which had commercial uses at ground floor level. A single storey snooker club building occupied the east part of the site. The site has been cleared, lying vacant for around ten years. The main part of the application site is relatively flat and currently surrounded by hoarding on the perimeter. The application site also includes a small section of open hardstanding to the western side of the entrance to the existing Woolmanhill student accommodation.

The surrounding area contains a mixture of uses with residential flats of mainly four storeys in height located to the north and east, five storey student accommodation (Woolmanhill flats) located to the west and the three storey Sandman Hotel located to the south. Also prominent in the surrounding streetscape is the now vacant former Woolmanhill Hospital complex that lies to the west.

### **Relevant Planning History**

Planning permission (Ref: 161427/DPP) was approved by the Planning Development Management Committee, following the conclusion of a legal agreement, in March 2017 for the erection of student accommodation (374 bed spaces) with associated infrastructure and landscaping. This permission was not implemented and has since expired.

Planning permission (Ref: 130579) was approved in October 2013 for a change of use and redevelopment to a Class 7 hotel (182 bedrooms) with associated food and beverage facility and associated parking, class 1 retail (375sqm). This permission was not implemented and has since expired.

An application (Ref: 090111) was withdrawn in October 2013 for a change of use to residential and development of 40 flats with associated parking. In addition, planning permission (Ref: A6/1811) was approved following an appeal in December 2009 for a change of use to residential & development of 50 no flats. This latter permission was not implemented and has since expired.

## **APPLICATION DESCRIPTION**

### **Description of Proposal**

The proposal seeks detailed planning permission for the erection of student accommodation with associated infrastructure and landscaping. The proposed development incorporates a “U” shaped building footprint orientated around a central courtyard area. The proposal comprises a range of building heights and would be 7 storeys in height fronting onto John Street (approximately 26.5m total height), 6 storeys in height within the eastern section of the site and 5 storeys in height along the northern boundary (approximately 16m total height). The proposal includes a range of setback elements to provide elevational interest. The highest part of the building is proposed as a ‘tower’ feature in the south east corner of the site. The main frontage of the building would be onto John Street, where an active frontage is proposed through the location of the main entrance and egress, and communal activity spaces. The internal courtyard area would be a shared amenity space for residents.

A variety of external materials are proposed include grey brick, a metal cladding (colour to be agreed via condition), dark grey curtain walling, glazing and a variety of doors at ground floor level.

In terms of access and parking, the main pedestrian and vehicular access to the site would be taken from John Street, pedestrian access on the southern building frontage and vehicular access from the west side of the site. The proposals would also include the provision of seven parking spaces. Five would be located at the western edge of the site with one of these utilised for EV charging and two further spaces would be adjacent to the courtyard and be utilised for disabled parking/ drop off. The proposals would also provide 140 secure cycle parking spaces along the eastern edge of the site. A number of hedges would be planted through the development, and eleven trees are shown on the landscaping plan.

## **Amendments**

The proposals have been revised since the original submission to take on board design amendments suggested by the Planning Service. This included alterations to the frontage of the building to create a more “active” frontage, amendments to the height of the ground floor elements, alterations to the courtyard layout, alterations to the western elevation, amendment to the location of parking spaces, alterations to the “tower” element on the southern elevation, alterations to the window design on the southern elevation and clarification/ amendment to the materials proposed throughout the development.

Further information was also submitted to address comments from consultees including a revised Flood Risk Assessment, further information on waste and cycle parking facilities and clarification on the levels of Developer Obligations sought.

## **Supporting Documents**

All drawings and supporting documents listed below can be viewed on the Council’s website at: <https://publicaccess.aberdeencity.gov.uk/online-applications/applicationDetails.do?activeTab=documents&keyVal=RTYWUMBZJ1B00>

- Indicative Student Management Plan – May 2023
- Pre-Application Consultation Report – May 2023
- Phase 1 Desk Study – May 2023
- Planning Statement – May 2023
- Planning Sustainability Statement – May 2023
- Drainage Assessment – May 2023
- Transport Statement – May 2023
- Noise and Vibration Survey Assessment – May 2023
- Design and Access Statement – Addendum – July 2023
- Flood Risk Assessment – July 2023
- Daylight and Sunlight Analysis Report – July 2023

## **Reason for Referral to Committee**

The application has been referred to the Planning Development Management Committee because it is a Major Development, subsequently the proposals fall out with the Scheme of Delegation.

## **Pre-Application Consultation**

The applicant undertook statutory pre-application consultation. The first public consultation event took place on the 8<sup>th</sup> February 2023, with the second event taking place on the 29<sup>th</sup> March 2023. Both of these events took place at Aberdeen Central Library, with both consultations lasting for two weeks after drop in events to allow for further questions, and submission of feedback forms.

Regular consultation also took place with the Community Council and a presentation was provided to George Street Community Council on the 11<sup>th</sup> April 2023. Local Councillors and neighbouring properties were also advised of the consultation events.

The applicant presented to the Council's Pre-Application Forum on the 20<sup>th</sup> April 2023. The presentation and accompanying PowerPoint slides provided an overview of the site location and history; the planning context of the site; the pre-application consultation and engagement timelines and community feedback worked into the design; key features of the development; site appraisal and contextual analysis and the overall vision of the proposed development. Councillors in attendance had the opportunity to indicate any initial issues they would like the applicants to consider and address in the submission of the planning application. The feedback from this meeting was worked into the design proposals where possible.

## **CONSULTATIONS**

**Police Scotland** – provided some general guidance noting that the site is in a low crime area and that due consideration should be given to crime reduction measures. They have suggested liaison with the police service prior to proceeding with the development and an informative can be added to the consent in this regard.

**ACC - Roads Development Management Team** – have no objection to the proposals following the submission of amended plans. Their response will be discussed in greater detail in the evaluation section of this report.

**ACC - Developer Obligations** – advised that contributions are required toward healthcare facilities (£132,595) and open space provision (£42,053).

**ACC - Environmental Health** – have provided various comments in relation to noise, air quality and dust management. Their response will be discussed in greater detail in the evaluation section of this report.

**ACC – Contaminated Land** – have reviewed the Desk Study Report and generally agree with the conclusions and recommendations. They did disagree with the assertion that human health risks can be discounted and asked that the proposed geo-environmental investigation (which would form a condition of the permission) takes account and builds on the information previously obtained.

**ACC - Structures, Flooding And Coastal Engineering** – have no objections to the proposal following the submission of a revised Flood Risk Assessment. Their response will be discussed in greater detail in the evaluation section of this report.

**ACC - Waste and Recycling** – have no objection following the submission of amended plans. Their response will be discussed in greater detail in the evaluation section of this report.

**Scottish Water** – unable to confirm if there is sufficient capacity at the Invercarnie Water Treatment Works and suggest that the developer contact them directly. Confirm that there is



sufficient capacity at the Nigg Waste Water Treatment Works. They also provided some general guidance on their assets in the surrounding area and confirmation that they will not accept any surface water connections into the combined sewer system.

**Scottish Environment Protection Agency** – note that the site lies within the SEPA Future Fluvial Flood Plain and that parts of the site lie within the SEPA Surface Water Flood Map. In particular, it is indicated that there may be potential for surface water flooding between the Gilcomston Burn open channel to the north and John Street. They supported the Flooding team’s requirement for further assessment on the source of flooding and provided recommendations on how these assessment could take place. SEPA also confirmed that if colleagues in flooding were content with the revised information there would be no further requirement to consult them on the proposals.

**Archaeology Service (Aberdeenshire Council)** – note that the application site falls within an area which has been subject to an archaeological evaluation in 2014 (undertaken by CFA Archaeology Ltd) which revealed no surviving archaeological features or artefacts of significance, and as such confirmed that they had no further comment to make in this instance.

**George Street Community Council** – no response received.

## **REPRESENTATIONS**

Two representations were received, both objecting to the application. The matters raised can be summarised as follows:

1. The first representation was generally content with the proposed development but requested a change to the northern boundary to remove the proposed timber fence and replace it with a brick wall or similar at a height of 1.8m;
2. The second representation raised concerns regarding the height of the building, and the potential for overshadowing properties in the surrounding area. The comment also disagreed with the applicant’s comment that the proposals would be a legible “marker” when viewed from distance along Denburn Road.

## **MATERIAL CONSIDERATIONS**

### **Legislative Requirements**

Sections 25 and 37(2) of the Town and Country Planning (Scotland) Act 1997 require that where making any determination under the planning acts, regard is to be had to the provisions of the Development Plan; and, that any determination shall be made in accordance with the plan, so far as material to the application, unless material considerations indicate otherwise.

Section 64 of the Planning (Listed Buildings and Conservation Areas) (Scotland) Act 1997 requires the planning authority to pay special attention to the desirability of preserving or enhancing the character or appearance of conservation areas.

### **Development Plan**

#### **National Planning Framework 4**

National Planning Framework 4 (NPF4) is the long-term spatial strategy for Scotland and contains a comprehensive set of national planning policies that form part of the statutory development plan. The relevant provisions of NPF4 that require consideration in terms of this application are –

- Policy 1: Tackling the climate and nature crises
- Policy 2: Climate mitigation and adaptation
- Policy 3: Biodiversity
- Policy 7: Historic assets and places
- Policy 9: Brownfield, vacant and derelict land and empty buildings
- Policy 12: Zero waste
- Policy 13: Sustainable transport
- Policy 14: Design, quality and place
- Policy 15: Local living and 20-minute neighbourhoods
- Policy 16: Quality homes
- Policy 22: Flood risk and water management
- Policy 24: Digital infrastructure
- Policy 27: City, town, local and commercial centres

#### Aberdeen Local Development Plan (2023)

The following policies are relevant –

- Policy WB2: Air Quality
- Policy WB3: Noise
- Policy NE4: Our Water Environment
- Policy D1: Quality Placemaking
- Policy D2: Amenity
- Policy D3: Big Buildings
- Policy D4: Landscape
- Policy D6: Historic Environment
- Policy R2: Degraded and Contaminated Land
- Policy R5: Waste Management Requirements for New Development
- Policy R6: Low and Zero Carbon Buildings, and Water Efficiency
- Policy H2: Mixed Use Areas
- Policy H7: Student Accommodation Developments
- Policy I1: Infrastructure Delivery and Planning Obligations
- Policy T2: Sustainable Transport
- Policy T3: Parking
- Policy CI1: Digital Infrastructure

#### **Interim Aberdeen Planning Guidance**

Aberdeen Planning Guidance is Interim Planning Guidance. The documents hold limited weight until they are adopted by the Council. The weight to be given to Interim Planning Guidance prior to its adoption is a matter for the decision maker. The following guidance is relevant –

- Air Quality
- Noise
- Materials: External Building Materials and Their Use in Aberdeen
- Student Accommodation
- Transport and Accessibility

- Flooding, Drainage and Water Quality
- Big Buildings
- Waste Management Requirements for New Development
- Resources for New Development
- George Street Masterplan (Draft)

## **EVALUATION**

### **Principle of Development**

Policy H2 (Mixed Use Areas) of the ALDP 2023 advises that *“applications for development or change of use within Mixed Use Areas must take into account the existing uses and character of the surrounding area and avoid direct conflict with the adjacent land uses and amenity. Where new housing is proposed, a satisfactory residential environment should be created which should not impinge upon the viability or operation of existing businesses in the vicinity.”*

In terms of the above, student accommodation can be considered to be a quasi-residential use, with the main differences being the temporary, typically annual basis of the tenancies and shared communal facilities (kitchen, living areas and associated facilities). In this case, the surrounding area contains a mixture of uses, including hotels, residential and business uses and for the reasons detailed below is not considered to have an adverse impact on the character or appearance of the surrounding area, nor on the function of any of the above mentioned uses. It is also noted that the provision of student accommodation on site, on a similar scale to that which is proposed, was previously found to be acceptable in 2017 and the redevelopment of the site for such purposes would be acceptable in principle when considered against Policy H2 of the ALDP 2023 and for the further reasons detailed below.

Policy H7 (Student Accommodation Developments) of the ALDP 2023 advises that *“proposals for new Student Accommodation development will be supported in principle where: the location is accessible by means of walking, cycling, wheeling and public transport to the university or college facilities; the proposals offer appropriate facilities; in particular providing an appropriate level of amenity space, refuse/ recycling storage space and secure bike storage facilities; and there will be no significant adverse impact to the amenity of the surrounding area.”*

The application site is located immediately adjacent to the defined city centre boundary and is accessible via varying modes of transport, being close to a number of bus routes, being within easy walking distance of the city centre and providing on site amenity space and storage facilities for a large number of future occupants. The proposals also provide facilities including communal areas, study areas and appropriate waste facilities. As is discussed later within this report the proposals also have no adverse impact on the amenity of the surrounding area and would therefore be in compliance with Policy H7 of the ALDP 2023.

The site is also adjacent to the Draft George Street Masterplan area, which as a draft Council strategy to guide the development and investment in the area was approved by Council for consultation in December 2022 and the Finalised Draft Masterplan is to be presented to Council on or before December 2023. The Vision of the Draft Masterplan is *‘George Street Connected! – The ‘local’ Neighbourhood: a vibrant, creative and inclusive city centre community at the heart of reinvention’*. The site is identified within the Draft Masterplan as an adjacent redevelopment opportunity and it is considered that the redevelopment of this site for student accommodation would accord with the aspirations of the Draft Masterplan by making a positive contribution to the vibrancy and vitality of the George Street area by increasing the number of residents in the area by c374 students, as well as bringing staff and visitors to the area.

Interim Aberdeen Planning Guidance (APG) in relation to Student Accommodation is also considered to be of relevance to this application. This states that the following points must be considered: the development meets an identified need for the type of development proposed; it should be in a location that is easily accessible to higher education by sustainable transport modes; it should be designed to have no adverse impact on the amenity of the surrounding area; layout standards and facilities within developments are of a high standard and the development has an appropriate management plan in place.

In this regard, as the applicants have scoped the market and considered that such a development would be beneficial for the area. Information contained within the supporting statement, which demonstrates that there is an overriding need for additional student accommodation options within the city, with circa 22,000 full time students in the city and only circa 8,500 purpose built student accommodation beds. The site is also easily accessible to Union Street, which in turn provides links to both Aberdeen University and Robert Gordon's University. The site is also within walking distance of the North East Scotland College and Aberdeen University. For the reasons detailed elsewhere in this report, the proposals would have no adverse impact on the character and amenity of the surrounding area, would provide study and communal areas as well as sufficiently large bedrooms and other associated facilities. A draft management plan forms part of the current application, which is found to be acceptable. A final management plan would be controlled via a suspensive condition. The proposals are therefore in accordance with the Interim APG on Student Accommodation.

### **Layout, Siting and Design**

Policy 14 (Design, quality and place) of NPF 4 states that "Development proposals will be designed to improve the quality of an area whether in urban or rural locations and regardless of scale" and "Development proposals will be supported where they are consistent with the six qualities of successful places: healthy, connected pleasant, distinctive, sustainable, adaptable" while Policy D1 (Quality Placemaking) of the ALDP 2023 advises that "*all development must ensure high standards of design, create sustainable and successful places*", and also reiterates the Scottish Government's six qualities of a successful place

In regards to the above, it is noted that a similarly sized and designed building was previously accepted for the site, although this permission was never implemented and has since expired. The proposed development proposes to utilise a number of materials, with brick for the main elevations along with elements of glazing and cladding and a tower feature which would sit more centrally within the site, aligned to the townscape of North St Andrew Street, and therefore provide an attractive focal point to the building when viewed from its main thoroughfares. The building has been designed with due consideration for its surrounding context, with the use of a variety of storey heights, setbacks and a tower focal feature. The Planning Service have suggested the insertion of a planning condition requiring large scale sample panels of each external material to ensure their appropriateness for the building, when viewed in context.

There were concerns noted with regard to the design of the proposed parapet, and how this element would look in reality; the design is however a requirement of the Noise Impact Assessment to limit the noise of the plant and was therefore an essential part of the proposal. This element is therefore considered to be acceptable in this instance.

The building is considered to promote healthiness, is well connected, would be distinctive in its design, would be sustainable and adaptable and would therefore meet the six qualities of successful places. There would be no conflict with either Policy D1 of the ALDP 2023 or with Policy 14 of NPF4.

Policy D2 (Amenity) of the ALDP 2023 advises that *“development will be designed to: make the most of any opportunities offered by the site to optimise views and sunlight through appropriate siting, layout and orientation; ensure that occupiers are afforded adequate levels of amenity in relation to daylight, sunlight, noise, air quality and immediate outlook; ensure that occupiers are afforded adequate levels of amenity in relation to daylight, sunlight, noise, air quality and immediate outlook; have a public face to the street to ensure natural surveillance, and active street frontages; ensure that refuse and recycling facilities, cycle storage, low and zero carbon technology, plant and services are sensitively integrated into the design; ensure that external lighting minimises light spillage into adjoining areas and the sky”*.

In this regard, it is noted that such a large building has the potential to have an adverse impact on the surrounding area, in particular the residential properties which are located to the west and north. It is noted that the proposals would impact on the levels of daylight and sunlight receipt and would introduce a level of overlooking which is not currently present (given the vacant brownfield nature of the site). The scope of these impacts is considered to be acceptable, with appropriate window to window distances and setbacks between the proposed building and those found in the surrounding area.

In addition, further information was submitted to ensure that all users of the building would receive acceptable levels of amenity, this including the provision of larger windows, the provision of larger internal communal amenity spaces and the provision of further daylight and sunlight analysis to ensure that the proposed courtyard area would receive appropriate levels of daylight. The amended and supporting information that has been submitted is considered to result in an acceptable level of amenity for occupants.

It should also be noted that the refuse and cycle facilities would be well integrated into the site, the development would utilise low and zero carbon technologies (controlled via condition) and that external lighting has been designed to ensure no light pollution into the surrounding area. Noise and air quality has also been considered (and is addressed below).

As a result of the above evaluation, there would be no conflict with Policy D2 (Amenity) of the ALDP 2023.

Policy D3 (Big Buildings) of the ALDP 2023 advises that *“big buildings must be of a high quality design which complements or improves the existing site context and that the most appropriate location for big buildings is within the city centre and its immediate periphery”*.

In this case, it is noted that the development is for the erection of an up to 7 storey building, which would represent a “big building” under the aforementioned policy. As discussed above, it has been concluded that the building has been designed with due consideration for its context, of a high quality design and sits on the immediate periphery of the defined city centre boundary. Consideration of the proposed building’s silhouette contribution to the city centre skyline, as well as views from key locations within the city centre, have been considered and are included within the supporting information and are found to be acceptable. The proposal is therefore in compliance with Policy D3 of the ALDP 2023.

Policy D4 (Landscape) of the ALDP 2023 advises that *“important views of the city’s townscape, landmarks and features when seen from busy or important publicly accessible vantage points such as roads, railways, recreation areas, and path networks and particularly from the main city approaches (gateways) will not be adversely affected by development.”*

In this case, the applicants have submitted various documents and photomontages of the development as proposed, showing the development from a number of viewpoints including the key view from the Denburn Viaduct looking northwards toward the site. These documents also indicate that the Bastille building, which is located to the rear of the Woolmanhill flats, would still be visible and the proposed building would not block the views of any other significant buildings within the city. There would be no conflict with Policy D4 of the ALDP 2023.

The site also sits adjacent to the boundary of the City Centre Conservation Area, which covers John Street itself and the buildings on its south side. Policy D6 (Historic Environment) of the ALDP 2023 seeks development that *“protects, preserves and enhances Aberdeen’s historic environment”*. This is similarly echoed in Policy 7 (Historic assets and places) of NPF4. The proposal involves an up to seven storey student accommodation development in an area that has a variety of uses and architectural styles, and diversity of building heights and forms. The design of the building is considered to be appropriate for its context and would make a positive contribution to the urban streetscape in this location for the reasons detailed above and would therefore have no significant impact on the character of the adjacent City Centre Conservation Area. The proposals are therefore in line with Policy D6 of the ALDP, nor with Policy 7 of NPF4.

Policy 9 (Brownfield, vacant and derelict land) of NPF4 advises that development proposals that will result in the sustainable reuse of brownfield land including vacant and derelict land and buildings, whether permanent or temporary, will be supported. Given that the proposal relates to such a brownfield site, which would see the construction of student accommodation on a long term vacant site, the proposals would comply with Policy 9 of NPF4.

Policy 15 (Local Living and 20 minute neighbourhoods) of NPF 4 advises: *“development proposals will contribute to local living including, where relevant, 20 minute neighbourhoods.”* The proposal is in close proximity to the city centre and has ample access to amenities within a 10 minute walk of the application site. The amenities of the George Street area, which functions as a neighbourhood centre as well being part of the city centre are also located in close proximity to the site. There would be no conflict with Policy 15 of NPF4.

## **Transport and Accessibility**

Policy T2 (Sustainable Transport) of the ALDP 2023 provides various guidance and seeks to *“minimise traffic generation, increase accessibility, encourage public transport and provide relevant infrastructure”* within the application site. Policy T3 (Parking) of the ALDP 2023 discusses matters such as parking within development and electric vehicle infrastructure. Policy 13 (Sustainable transport) of NPF4 provides similar guidance and advises that development will be supported where it has been designed in association with sustainable travel, provides direct links to local facilities, will be accessible by public transport, provide electric vehicle charge points, provide safe and convenient cycle parking and consider the needs of all users, as well as mitigate the impact of development on local transport routes.

In terms of walking, it is the site is considered to be in a highly accessible location, being a four minute walk from North East Scotland Colleges’ Gallowgate Campus and 23 minutes from Aberdeen University. In terms of cycling, it is noted that a number of dedicated cycle storage facilities are to be provided, the 140 spaces proposed exceed those required (128) and are considered to be acceptable. Implementation of such would be controlled via condition. It is concluded that the site is considered good for all modes of sustainable and active travel, such as walking, wheeling and cycling.

In terms of public transport, it is noted that a bus stop sits immediately adjacent to the site and the site is also within walking distance of the city centre, which provides access to regular bus

services to both universities. It is also proposed to upgrade the bus stops which sit immediately adjacent to the site and a condition is proposed in this regard, the upgrades will be either via a financial contribution or physical upgrades themselves, which are to be agreed with the Public Transport Unit. It is concluded that the site is considered good from a public transport perspective. A residential travel pack would also be required as a condition of the planning permission.

In terms of parking, it is noted that the proposals are for 4 parking bays, 2 disabled bays and 1 EV charging bay. The standard bays are to be available for staff only, with the disabled bays also utilised as a drop off facility at the beginning and end of term time only. The site is also within a controlled parking zone and any inappropriate parking would be enforced accordingly. A Vehicle Management Plan has also been submitted by the applicant and accepted by colleagues in Roads Development Management.

The proposals have been reviewed by colleagues in Roads Development Management, who have raised no objection following the submission of amended plans. A condition has also been inserted to ensure that the required bus stop upgrades are completed prior to the occupation of the development. The proposal would accordingly be in compliance with Policy 13 of NPF4 and Policies T2 and T3 of the ALDP 2023.

### **Flooding, Drainage and Water Quality**

Policy 22 (Flood risk and water management) of NPF 4 advises that “development proposals will: not increase the risk of surface water flooding to others, or itself be at risk. manage all rain and surface water through sustainable urban drainage systems (SUDS), presume no surface water connection to the combined sewer; seek to minimise the area of impermeable surface, provide a connection to the public sewers and create, expand or enhance opportunities for natural flood risk management, including blue and green infrastructure”.

Policy NE4 (Our Water Environment) of the ALDP 2023 advises that development will not be supported on sites where there would be an increased risk of flooding both within and outwith the site, that adequate provision should be made for the maintenance of watercourses and would not require the construction of new or strengthened flood defences. In addition, there is a requirement for a Flood Risk Assessment, foul drainage and water connection to the public sewerage system and that all new developments are required to incorporate Sustainable Urban Drainage Systems (SUDS) to manage surface water.

In relation to the above, a Flood Risk Assessment (FRA) and various documents in relation to site drainage have been submitted in support of the planning application. Colleagues in the Flood Prevention Unit (FPU) and SEPA requested the submission of further information to demonstrate that the new development would not be at flood risk from a potential blockage of an existing rubbish/ debris screen at the nearby Gilcomston Burn.

An updated FRA was submitted which noted that the site had a 0.1% chance of flooding, that the levels of the existing roads would convey any floodwater away from the site, that there was a 0.1-0.5% chance of surface water occurring on the pre-development site and that the proposed surface water system would contain flows generated by a critical 200 year storm, subject to maintenance. Colleagues in FPU also noted that the discharge rate of the new development to the nearby watercourse was agreed.

The above conclusions were considered to be acceptable and colleagues in the FPU raise no objection to the proposal, this resulted in colleagues in SEPA not requiring further consultation on the proposals. A condition will be inserted to ensure that the development is carried out in

accordance with the recommendations of the FRA which in turn would ensure compliance with Policy NE4 of the ALDP 2023 and with Policy 22 of NPF4 along with any relevant guidance.

## **Waste Management**

Policy 12 (Waste) of NPF4 advises that *“development proposals will seek to reduce, reuse, or recycle materials in line with the waste hierarchy.”* Policy R5 (Waste Management Requirements for New Developments) of the ALDP 2023 advises *“all new developments should have sufficient space for the storage of general waste, recyclable materials and compostable wastes where appropriate”*.

The proposals relate to a vacant site, where there would be no scope for re-use or removal of any materials in order to facilitate the development. The applicants have also provided an amended “bin store plan” which shows 12 general waste containers, 25 mixed recycling containers and three food waste containers. Access to such would be taken directly from John Street. The proposals have been subject to consultation with colleagues in Waste Management, who following the submission of the revised plans confirmed their acceptability, with access to the bin store provided directly from John Street. The proposal is therefore considered to have provided sufficient space for the storage of waste facilities, which in turn would ensure compliance with Policy 12 (Waste) of NPF4, Policy R5 (Waste Management Requirements for New Development) of the ALDP 2023 and with its associated Interim Aberdeen Planning Guidance: Resources for New Development.

## **Developer Obligations**

Policy I1 (Infrastructure Delivery and Planning Obligations) of the ALDP 2023 advises that in order to *“create sustainable communities, development must be supported by the required infrastructure, services and facilities to deliver the scale and type of developments proposed.”* In this regard, the proposal has been subject to consultation with colleagues in Developer Obligations, who have advised that contributions are required toward healthcare facilities (£132,595) and open space provision (£42,053). The applicants have agreed to these contributions, payment of which would be subject to a legal agreement. The provision of such would ensure compliance with Policy I1 of the ALDP 2023 and its associated guidance: Planning Obligations.

## **Air Quality**

Policy WB2 (Air Quality) of the ALDP 2023 advises that *“development proposals which may have a detrimental impact on air quality will not be permitted unless measures to mitigate the impact of air pollutants are proposed and agreed with the Planning Authority”*.

In terms of air quality, the proposals have been assessed by colleagues in Environmental Health, who noted that the site is located approximately 500 metres to the west of the nearest Air Quality Management Area (AQMA) on East North Street, and consider that there would be no adverse impact as a result of the development. The response also considered vehicle movements associated with the proposal, and also noted that due to the nature of development proposed there would also be no adverse impact on air quality.

In addition, it is noted that occupants of the surrounding residential properties could be exposed to dust during each phase of works. Colleagues in Environmental Health have therefore requested the submission of an Air Quality Dust Risk Assessment and Dust Management Plan. Both of these could be controlled via an appropriately worded planning condition. Subject to this, there would be



no conflict with Policy WB2: Air Quality of the ALDP 2023 or its associated Interim Aberdeen Planning Guidance: Air Quality.

## **Noise**

Policy WB3 (Noise) of the ALDP 2023 advises that *“in cases where significant exposure to noise is likely to arise from development, a Noise Impact Assessment (NIA) will be required as part of a planning application.”*

In terms of noise, an Noise Impact Assessment (NIA) was submitted in support of the proposals, which has also been assessed by colleagues in Environmental Health. They have accepted the report and the proposed development, provided the noise mitigation measures proposed are installed, which include glazing and trickle ventilators, a 3 metre high parapet wall, a restriction on the number of Air Source Heat Pumps and the installation of sound absorbing materials. Compliance with the NIA will be controlled via an appropriately worded planning condition, which would ensure compliance with Policy WB3: Noise of the ALDP 2023 and its associated IAPG: Noise. An informative will also be added in relation to the hours of construction.

## **Contaminated Land**

Policy R2 (Degraded and Contaminated Land) of the ALDP 2023 requires that all land that is degraded or contaminated, including visually, is either restored, reclaimed or remediated to a level suitable for its proposed use. In this case, the applicants submitted a Desk Study Report that recommended that a full geo-environmental assessment be carried out, road and pavement designs should be considered and testing for the water mains should be carried out. This can be controlled as a condition of the planning permission. They also requested that further assessment of this aspect be included within the geo-environmental assessment. Subject to this, the proposal would be in compliance with Policy R2 of the ALDP 2023.

## **Tackling the Climate and Nature Crises, Climate mitigation and Biodiversity**

Policy 1 (Tackling the Climate and Nature Crises) of NPF4 requires significant weight to be given to the global climate and nature crises in the consideration of all development proposals. Policy 2 (Climate mitigation and adaptation) of NPF4 requires development proposals to be designed and sited to minimise lifecycle greenhouse gas emissions as far as possible, and to adapt to current and future risks from climate change. Policy 3 (Biodiversity) of NPF4 requires proposals for local development to include measures to conserve, restore and enhance biodiversity, proportionate to the nature and scale of development.

The proposed development, which relates the redevelopment of a city centre brownfield site would ensure that the site and the wider area are more sustainable in meeting local needs, occupants are able to utilise local transport routes and the building would be subject to the highest sustainability standards to ensure compliance with Policies 1 and 2 of NPF4. The proposed development is small-scale to a certain extent and although it does not offer the opportunity for meaningful biodiversity gain, areas within the site are to be planted with hedges and a small number of trees are to be planted throughout the development and the proposals are considered to be acceptable and in line with Policy 3 of NPF4.

## **Low and Zero Carbon Buildings**

Policy R7 (Low and Zero Carbon Buildings, and Water Efficiency) of the ALDP 2023 requires all new buildings to meet at least 20% of the building regulations carbon dioxide emissions reduction target applicable at the time of the application through the installation of low and zero carbon

generating technology in accordance with the associated supplementary guidance. The policy also requires all new buildings to use water saving technologies and techniques. Conditions can be attached requiring details to be submitted demonstrating that the buildings would comply with these requirements.

## **Digital Infrastructure**

Policy CI1 (Digital Infrastructure) of the ALDP 2023 advises that *“all new commercial development and residential development where five or more units are proposed will be expected to have access to high-speed communications infrastructure.”* Whereas Policy 24 (Digital Infrastructure) of NPF4 advises that: *“development proposals that incorporate appropriate, universal, and future-proofed digital infrastructure will be supported.”*

The site within an urban area adjacent to the city centre boundary, and a check of the OFCOM website confirms that the area has access to standard, superfast and ultrafast broadband. A condition would also be added to the consent to ensure that the student accommodation is provided access to these facilities. Subject to the above the proposals would comply with Policy CI1 of the ALDP 2023 and Policy 24 of NPF4.

## **Matters Raised in Representations**

One representation was generally content with the proposed development but requested a change to the northern boundary to remove the proposed timber fence and replace it with a brick wall or similar and a height of 1.8m. *Response: the boundary treatments, as proposed (being timber fencing), are considered to be acceptable, and a brick wall is not seen an essential requirement.*

A further representation raised concerns regarding the height of the building, and the potential for overshadowing properties in the surrounding area. This submission also disagreed with the applicant’s comment that the proposals would be a legible “marker” when viewed from distance along Denburn Road. *Response: the height of the building, along with the impact on neighbouring properties has been discussed elsewhere in this report. The design and scale of the building is considered to be appropriate in this instance.*

## **RECOMMENDATION**

Approve Conditionally & Subject to Legal Agreement

## **REASON FOR RECOMMENDATION**

The proposed building has been designed with due consideration for its context and would have no adverse impact on the character or amenity of the surrounding area, being of an appropriate size scale and design, with the proposed use as student accommodation considered to be acceptable within this mixed use setting. All relevant technical considerations have been resolved, or can be controlled via appropriately worded planning conditions. The proposal is therefore in accordance with Policies 1: Tackling the climate and nature crises, 2: Climate mitigation and adaptation, 3: Biodiversity, 7: Historic assets and places, 9: Brownfield, vacant and derelict land and empty buildings, 12: Zero waste, 13: Sustainable transport, 14: Design, quality and place, 15: Local living and 20-minute neighbourhoods, 16: Quality homes, 22: Flood risk and water management, 24: Digital infrastructure of National Planning Framework 4 and with Policies WB2: Air Quality, WB3: Noise. NE4: Our Water Environment, D1: Quality Placemaking, D2: Amenity, D3: Big Buildings, D4: Landscape, D6: Historic Environment, R2: Degraded and Contaminated Land, R5: Waste Management Requirements for New Development, R6: Low and Zero Carbon Buildings, and Water Efficiency, H2: Mixed Use Areas, H7: Student Accommodation

Developments, I1: Infrastructure Delivery and Planning Obligations, T2: Sustainable Transport, T3: Parking and CI1: Digital Infrastructure of the Aberdeen Local Development Plan 2023.

## **CONDITIONS**

### **(01) DURATION OF PERMISSION**

The development to which this notice relates must be begun not later than the expiration of 3 years beginning with the date of this notice. If development has not begun at the expiration of the 3-year period, the planning permission lapses.

Reason - in accordance with section 58 (duration of planning permission) of the 1997 act.

### **(02) MATERIALS**

That no development shall take place unless a scheme detailing all external finishing materials to the roof and walls of the development hereby approved, including large scale sample boards of the proposed brick and all elements cladding and window detailing, along with further details of the design features to both the bin store and office building at ground floor level has been submitted to, and approved in writing by the planning authority and thereafter the development shall be carried out in accordance with the details so agreed.

Reason - in the interests of visual amenity.

### **(03) PARKING/ CYCLE PARKING AND BIN STORAGE IN ACCORDANCE WITH APPROVED PLANS**

That the development hereby approved shall not be occupied unless the car parking, cycle parking and bin storage areas hereby granted planning permission have been constructed, drained, laid-out and demarcated in accordance with drawing No. 12483-HFM-B1-XX-DR-A-02 010 P02 and 12483-HFM-B1-XX-DR-A-02 051 P03 of the plans hereby approved or such other drawing as may subsequently be submitted and approved in writing by the planning authority. Such areas shall not thereafter be used for any other purpose other than the purpose of the parking of cars ancillary to the development and use thereby granted approval.

Reason - in the interests of public safety and the free flow of traffic and to ensure that the site is adequately serviced.

### **(04) AIR QUALITY DUST RISK ASSESSMENT**

That no development shall take place (including site stripping or service provision) unless an Air Quality (Dust) Risk Assessment for the construction phase of development has been submitted to and approved in writing by the Planning Authority. Such risk assessment shall be carried out by a suitably qualified consultant in accordance with the Institute of Air Quality Management document "Guidance on the Assessment of Dust from Demolition and Construction 2014". Thereafter development shall be carried out in accordance with the approved plan.

Reason: in order to control air pollution from dust associated with the development in accordance with Policy WB2: Air Quality of the Aberdeen Local Development Plan 2023.

### **(05) DUST MANAGEMENT PLAN**

That no development (including site stripping or service provision) shall take place unless a Dust Management Plan for the construction phase of development has been submitted to and approved in writing by the planning authority. Such management plan shall specify dust mitigation measures and controls, responsibilities, and any proposed monitoring regime. Thereafter development (including demolition) shall be undertaken in accordance with the approved plan.

Reason - In order to control air pollution from dust associated with the construction of the development in accordance with Policy WB2: Air Quality of the Aberdeen Local Development Plan 2023.

#### (06) NOISE IMPACT ASSESSMENT COMPLIANCE

That the development hereby approved shall not be occupied unless the noise mitigation measures have been installed in accordance with the conclusions and recommendations set out in the approved Noise Impact Assessment (Sandy Brown Limited (Reference: 23119-R01-B, Version B Date: 28 Apr 23) and evidence of this installation has been provided to, and agreed in writing by, the Planning Authority. For avoidance of doubt this should include the following:

- a) Section 7.1, table 6 and associated figure 7 regarding glazing and trickle ventilators.
- b) Section 7.3.1 regarding provision of the rooftop 3 metre high parapet wall.
- c) Section 7.3.1 regarding the number of Air Source Heat Pumps limited to 6 units.
- d) Section 7.3.3 and Compliance with the octave band centre frequency data for plant (super Low Noise Unit) WSAN-YSC4 EN, Lw (dB) contained within table 7, lining of parapet with a suitable sound absorbing material and noise levels from any ventilation louvres grilles etc associated with the proposed heating plant room should not exceed NR 50 at 3 m distance.

Once installed the mitigation measures shall be retained in perpetuity.

Reason: in the interests of amenity and to ensure compliance with Policy WB3: Noise of the Aberdeen Local Development Plan 2023.

#### (07) FULL FIBRE BROADBAND

That the development hereby approved shall not be occupied unless a scheme for the provision of a full fibre broadband connection to the building has been submitted to and approved in writing by the planning authority. Thereafter the scheme shall be implemented as approved and all rooms within the student accommodation provided with a full fibre broadband connection.

Reason – in order to provide all flats with access to high-speed communications infrastructure, in accordance with the requirements of Policy CI1 (Digital Infrastructure) of the Aberdeen Local Development Plan 2023 and Policy 24 (Digital infrastructure) of National Planning Framework 4.

#### (08) LOW AND ZERO CARBON

No development shall take place unless a scheme detailing compliance with the Council's Resources for New Development Guidance has been submitted to and approved in writing by the Planning Authority. Thereafter no units shall be occupied unless the recommended measures specified within that scheme for that unit for the reduction of carbon emissions have been implemented in full.

Reason - to ensure that the development complies with requirements for reductions in carbon emissions specified in the City Council's relevant published Interim Planning Advice: Resources for New Development.

#### (09) FLOOD RISK ASSESSMENT COMPLIANCE

That the development hereby approved shall not be occupied unless carried out in full accordance with the conclusions and recommendations set out in the approved Flood Risk Assessment (Fairhurst Reference: 152031 - FRA 02 ISS 03 Date 2<sup>nd</sup> June 2023) and evidence of this compliance has been provided to, and agreed in writing by, the Planning Authority.

Reason: to ensure that the site can be adequately drained and to ensure that the site is not susceptible to flooding.

#### (10) GREEN TRAVEL PLAN

That the development hereby approved shall not be occupied unless there has been submitted to and approved in writing by the Planning Authority a detailed Green Transport Plan, which outlines sustainable measures to deter the use of the private car, in particular single occupant trips and provides detailed monitoring arrangements, modal split targets and associated penalties for not meeting targets.

Reason - in order to encourage more sustainable forms of travel to the development.

#### (11) STUDENT MANAGEMENT PLAN

That prior to the occupation of the development hereby approved, a student management plan shall be submitted to and approved in writing by the Planning Authority and the use shall be undertaken in accordance with the details so approved and shall be so maintained. The management plan shall include details on health and safety standards and procedures; maintenance and repairs; environmental quality; landlord and tenant relationship; student welfare; anti-social behaviour and disciplinary procedures; and administration and compliance procedures.

Reason - To ensure a satisfactory standard of accommodation is provided and in the interests of the amenity of the area.

#### (12) GEO ENVIRONMENTAL ASSESSMENT

Prior to the commencement of the development hereby approved, a Geo-Environmental Assessment, which follows the conclusions and recommendations of the submitted Desk Top Survey (Ref: 152031 01), shall be submitted to and approved by the Planning Authority. For avoidance of doubt, the survey shall also include an assessment on human health risks.

Reasons – to ensure that the site remains suitable for human occupation.

#### (13) BUS STOP UPGRADES

That prior to the occupation of the student accommodation hereby approved, details of bus stop upgrades to the existing facilities on John Street shall be submitted to and approved in writing by the Planning Authority. Prior to the discharge of this condition, confirmation shall be sought from the Council's Public Transportation Unit that such upgrades are acceptable, or are not required. Thereafter the agreed works shall be implemented in accordance with an approved scheme and implemented prior to occupation.

Reason: to ensure that the development would have access to more sustainable modes of transportation.

## **ADVISORY NOTES FOR APPLICANT**

1. In order to protect amenity of the occupants of the neighbouring residences from noise produced as a result of demolition, site/ground preparation works and construction works operations creating noise which is audible at the site boundary should not occur outside the hours of 07:00 to 19:00 Monday to Friday and 08:00 to 13:00 on Saturdays. No works shall be undertaken on a Sunday.
2. The developer should liaise with the Police Scotland Architectural Liaison Officer service at each stage of development, for the purpose of designing out crime using the principles of Crime Prevention through Environmental Design (CEPTED).
3. The applicant should could “Secured by Design” awards and Police Scotland have recommended that the development should achieve the Police SBD award.